

TO:

**SUPERSEDED BY EI 94-010
EFFECTIVE 8/18/94**

ENGINEERING INSTRUCTION

NEW YORK STATE DEPARTMENT OF TRANSPORTATION

SUBJECT: REBUILDING NEW YORK
WORK ZONE SIGNS

Subject Code: 7.27-1-619

Distribution:

30 Main Office 33 Regions 34 Special

Code: 85-22

Date: 3-29-85

Supersedes:

APPROVED:

R. H. Edwards
R. H. EDWARDS, Facilities Design Div. Deputy Chief Engr

Item 15619.9901, Rebuilding New York Work Zone Sign has been inserted into 100% State financed contracts since the March 22, 1984 letting. The Item was distributed under EI 84-24 which contains the policy for its use. This item requires the Contractor to turn over the Work Zone signs at the end of the project and since its institution in 1984, some regions have built up a considerable supply of these signs and now may wish to either:

- (1) Have the contractor furnish, install and remove and dispose of work zone signs like any other construction sign, or;
- (2) Have the Contractor install and return State supplied signs.

If yours is one of the Regions that have enough signs, either of the attached specifications may be used. They provide for procurement of the "Rebuilding New York" work zone signs. The special specifications are for use on 100% State projects as were detailed in EI 84-24. One specification, 15619.9910 is for Contractor supplied and erected signs while the other, 15619.9911 is for State supplied and Contractor erected signs. In all other respects, there is no change in the application of the specification.

The new specifications (15619.9910 and 15619.9911) may be used starting with the letting of August 8, 1985 . They are Main Office inserts.

L 8-8-85

PREL	FINAL
DESIGN	LANDSCAPE
RECEIVED FACILITIES DESIGN DIVISION	
APR 09 1985	
CIRC.	FILE

15619.9910
& Disposal)

REBUILDING NEW YORK WORK ZONE SIGN (Including Removal

Description. The Contractor shall furnish, install, maintain and remove the sign detailed herein, and its mounting at the locations shown in the Contract Documents or where directed by the Engineer.

Materials. The panel material may be of any material permitted under subsection 619-2.02 of the Standard Specifications. The sign support and mounting shall meet the requirements of subsection 619-3.02. Sheeting shall meet the specifications of subsection 730-05.01 (class A).

Construction Details. The sign detailed below shall be installed and maintained at all locations where long duration (overnight) construction signs are installed. Signs shall be installed 300 feet $\pm$ in advance of the first warning sign of a series of construction signs. The sign shall be installed on each approach to a work zone where such a series of construction signs is installed. However, on roadways under construction for several miles where several individual work sites may occur within the project limits, only one "Rebuilding New York Work Zone" sign need be installed at each project limit, facing traffic entering into the project area.

The back of the panel shall be painted as required under subsection 619-3.02, Construction Signs.

Signs damaged or otherwise unusable during the course of the contract shall be repaired or replaced promptly.

Upon completion of the contract or when directed by the Engineer the signs shall be removed. The mountings and panels shall become the property of the Contractor and disposed of by him in a manner satisfactory to the Engineer.

Method of Measurement. Rebuilding New York Work Zone Sign will be measured for payment as the number of signs furnished, installed, maintained (ie, repaired or replaced) and removed.

Basis of Payment. The unit price bid for each REBUILDING NEW YORK WORK ZONE SIGN shall include the cost of all labor, equipment, and materials necessary to perform the work including the repair or replacement of damaged or unusable signs. 70% of the price bid will be paid upon installation. The remainder is to be paid upon maintenance and removal.

A sign, installed at more than one location on the Contract, shall be eligible for payment only once.

15619.9911
by State)

REBUILDING NEW YORK WORK ZONE SIGN (Panel Furnished

Description. The Contractor shall install, on mountings he provides, maintain, remove and store the sign detailed herein, at the locations shown in the Contract Documents or where directed by the Engineer.

Materials. The panel will be furnished by the State at the project site. The sign support and mounting shall meet the requirements of subsection 619-3.02.

Construction Details. The sign detailed below shall be installed on mountings provided by the Contractor and maintained at all locations where long duration (overnight) construction signs are installed. Signs shall be installed 300 feet $\pm$ in advance of the first warning sign of a series of construction signs. The sign shall be installed on each approach to a work zone where such a series of construction signs is installed. However, on roadways under construction for several miles where several individual work sites may occur within the project limits, only one "Rebuilding New York Work Zone" sign need be installed at each project limit, facing traffic entering into the project area.

Upon completion of the contract or when directed by the Engineer the sign panels shall be removed and stored at the locations directed and shall become the property of the State. The mountings shall become the property of the Contractor and disposed of by him in a manner satisfactory to the Engineer.

Signs damaged or otherwise unusable during the course of the contract shall be repaired or replaced promptly.

Method of Measurement. Rebuilding New York Work Zone Sign will be measured for payment as the number of signs, installed, maintained (ie, repaired or replaced), removed and stored.

Basis of Payment. The unit price bid for each REBUILDING NEW YORK WORK ZONE SIGN shall include the cost of all labor, equipment, and materials necessary to perform the work including the repair or replacement of damaged or unusable signs. 70% of the price bid will be paid upon installation. The remainder is to be paid upon maintenance, removal and storage.

A sign, installed at more than one location on the Contract, shall be eligible for payment only once.